

Consulate of the United States of America  
Fukuoka, Japan



April 2, 2021

To: Prospective Offerors:  
From: Andrew T. Staples, Contracting Officer  
Subject: Request for Quotations Number 19JA25-21-Q-0061 Q&A No.1  
Roof Repair Services

In response to questions received in regard to the referenced Request for Quotations, the Contracting Officer is disseminating the following information.

**Question 1:**

About 3.9.2. Metal Coping Installation

Are all existing Coping replaced? (Is the part without the conduit replaced?)

Would you like to replace the part without the conduit with the same size?

**Answer 1:**

There are two pieces of metal coping installed; a vertical metal coping on the exterior of the roof wall/fascia, and the top metal coping. No vertical metal coping will be replaced. All top metal coping will be replaced, including the portions without conduit. The extra-wide top metal coping will only be used where the conduit is run (south and east wall, terminating at the last spotlight); the rest of the top metal coping will be the same size as the current installation.

-End of Q&A Correspondence No.1-